BRUHATH BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of Work : IMPROVEMENTS TO ROAD AND DRAIN AT KEMPEGOWDA GARDEN AND SAPTHAGIRI LAYOUT IN WARD NO. 12, SHETTYHALLI SUB DIVISION

Sl. No	Description	Unit	Qty	Rates	
				In Figs	In Words
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 metres and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per spe., to lead of 0 to 9 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per the direction of engneer in charge of the work	Cum	672.60	208.82	Rupee two hundred eight and eighty-two paise only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications	Cum	92.61	5159.02	Rupee five thousand, one hundred fifty-nine and zero two paise only
3	Design mix M 20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @ 0.46 cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008 i) upto 5m height	Cum	214.38	6965.26	Rupee six thousand, nine hundred sixty-five and twenty-six paise only
4	Supplying, fitting and placing TMT bar reinforcement in sub-structure as per drawing and Technical Specifications complete as per specifications. MORTH Specification No.1600 & 2200 TMT Bars FE 500	Tonne	13.01	74331.44	Rupee seventy-four thousand, three hundred thirty-one and forty-four paise only
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	1682.70	310.58	Rupee three hundred ten and fifty-eight paise only

EXECUTIVE ENGINEER-4
BBMP CONTRACTION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl. No	Description	Unit	Qty	Rates	
				In Figs	In Words
6	Supplying and fixing precast reinforeced concrete slab 10cm thick of mix M20 using 20mm and downsize graded granite metal using reinforecement 10mm dia steel at 150mm c/c bothways cost , transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveynce charge labour charges inclusive of cost of all materisl	Sqm	559.29	1680.00	Rupee one thousand, six hundred eighty only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-560057

Signature of the Contractor

Executive Engineer
Dasarahalli Division